

Level: Level 0 · Internal condition: TM59_Bathroom

SIMULATION RESULTS

Source	Tas (TSD)
Results converted	27 Aug 2026 18:38
Model vs results no provenance record	not recorded
Heating design day	Leeds_TRY ANN HTG 100% CONDS DB
Cooling design day	Leeds_TRY ANN CLG 0% CONDS DB=>GRad

DESIGN CRITERIA

	Heating	Cooling
Room set point	60.8 °F	302.0 °F
Outdoor dry bulb	—	—
Outdoor RH (coincident)	—	—

ROOM HUMIDITY

Humidification set point lower RH limit	—
Dehumidification set point upper RH limit	—

HEATING AND COOLING LOADS

	Heating	Cooling
Design load (Tas sizing, TBD)	0 Btu/h	0 Btu/h
Design-day peak (TSD)	3,889 Btu/h	0 Btu/h
Annual simulated peak (TSD)	355 Btu/h	0 Btu/h

Design load: zone maximum from Tas sizing (TBD). Design-day and annual peaks: Tas simulation (TSD). Shown side by side; no pass/fail rule is applied.

CONDITIONS AT PEAK

	Heating		Cooling	
	Design day	Annual	Annual	Annual
Time	hour 24 of design day	23 Dec 09:00–10:00	n/a	n/a
Room air temperature	60.8 °F	60.8 °F	n/a	n/a
Room resultant temperature	57.0 °F	60.7 °F	n/a	n/a
Room relative humidity	—	35 %	n/a	n/a
Outdoor dry bulb	—	27.9 °F	n/a	n/a
Outdoor relative humidity	—	100 %	n/a	n/a

Annual times are Tas simulation hours (hour-ending, local standard time, no DST, 365-day year). A design-day peak has no calendar date.

ZONE HEAT BALANCE AT PEAK

Tas zone term	Heating		Cooling
	Design day (Btu/h)	Annual (Btu/h)	Annual (Btu/h)
Solar	—	0	n/a
Lighting	—	0	n/a
Occupancy (sensible)	—	0	n/a
Equipment (sensible)	—	0	n/a
Infiltration / ventilation	-381	-319	n/a
Air movement (inter-zone)	0	0	n/a
Building heat transfer	-3,491	-11	n/a
External conduction — opaque	-16	-26	n/a
External conduction — glazing	0	0	n/a
Net (heating: = -load)	-3,889	-355	n/a

Tas zone heat-balance terms at the peak hour: + gain to the room air, - loss. Latent terms are not included.