

SPACE DESIGN LOAD SUMMARY

Level 03 — Open-plan Office North-East Wing
incl. Breakout / Kitchenette Zone B (Tenant
Fit-out Cat A)

Level: Level 0 · Internal condition: —

DESIGN GATE

ILLUSTRATIVE VALUES for layout stress only: Bathroom_2 results scaled ×118 and an invented cooling peak. Not from any result file.

SIMULATION RESULTS

Source	Tas (TSD)
Results converted	27 Aug 2026 18:38
Model vs results	not recorded
no provenance record	
Heating design day	Leeds_TRY ANN HTG 100% CONDS DB
Cooling design day	Leeds_TRY ANN CLG 0% CONDS DB=>GRad

DESIGN CRITERIA

No set point profiles and no design days in model

HEATING AND COOLING LOADS

	Heating	Cooling
Design load (Tas sizing, TBD)	134.51 kW	24.10 kW
Design-day peak (TSD)	134.50 kW	23.45 kW
Annual simulated peak (TSD)	12.27 kW	19.88 kW

Design load: zone maximum from Tas sizing (TBD). Design-day and annual peaks: Tas simulation (TSD). Shown side by side; no pass/fail rule is applied.

CONDITIONS AT PEAK

	Heating		Cooling	
	Design day	Annual	Annual	
Time	hour 24 of design day	23 Dec 09:00–10:00	17 Jul 15:00–16:00	
Room air temperature	16.0 °C	16.0 °C	24.1 °C	
Room resultant temperature	13.9 °C	15.9 °C	25.3 °C	
Room relative humidity	—	35 %	52 %	
Outdoor dry bulb	—	-2.3 °C	28.4 °C	
Outdoor relative humidity	—	100 %	41 %	

Annual times are Tas simulation hours (hour-ending, local standard time, no DST, 365-day year). A design-day peak has no calendar date.

ZONE HEAT BALANCE AT PEAK

Tas zone term	Heating		Cooling
	Design day (kW)	Annual (kW)	Annual (kW)
Solar	—	0.00	9.12
Lighting	—	0.00	2.21
Occupancy (sensible)	—	0.00	3.38
Equipment (sensible)	—	0.00	4.71
Infiltration / ventilation	-13.18	-11.02	0.61
Air movement (inter-zone)	0.00	0.00	-0.12
Building heat transfer	-120.74	-0.37	1.54
External conduction — opaque	-0.57	-0.88	1.83
External conduction — glazing	0.00	0.00	1.74

Tas zone term	Heating		Cooling
	Design day (kW)	Annual (kW)	Annual (kW)
Net (heating: = -load)	-134.50	-12.27	25.02

Tas zone heat-balance terms at the peak hour: + gain to the room air, – loss. Latent terms are not included.